

# Attachment A



Owner: City of Maple Grove, P. O. Box 1180, Maple Grove, MN 55369	Date: February 9, 2022
Contractor: Kuechle Underground, Inc., 10998 State Hwy 55, P.O. Box 509, Kimball, MN 55353	
Bond Co: Employers Mutual Casualty Company, 717 Mulberry, Des Moines, IA 50309	Bond No: S026634

**CHANGE ORDER NO. 1**  
 TRI-CARE 4TH ADDITION  
 STREET AND UTILITY IMPROVEMENTS  
 STANTEC PROJECT NO. 193805295  
 CITY PROJECT NO. CP 21-11

**Description of Work**

This Change Order provides compensation to the Contractor for additional work and cost required to add the additional 2% of iron fillings to the Biofiltration Media within the pond per the Developer's direction. This is required for the final watershed approval for the Developer. The original percentage of iron fillings included in the media per the plan was 3%. This will now be increased to 5%. This Change Order also provides compensation to the Contractor for the revision of the storm sewer on the project due to pond modifications as well as a value engineering effort to decrease storm sizing and cost on the project.

This Change Order provides for all material and labor costs and no additional compensation will be provided to the Contractor for this additional work.

No.	Item	Unit	Contract Quantity	Unit Price	Total Amount
<b>PART 1 - BIOFILTRATION MEDIA REVISIONS</b>					
1	BIOFILTRATION MEDIA (CV) - ADDITIONAL 2% IRON FILLINGS	CY	275	\$61.00	\$16,775.00
	<b>TOTAL PART 1</b>				<b>\$16,775.00</b>
<b>PART 2 - STORM SEWER MODIFICATIONS (DEDUCTIONS)</b>					
2	30" RCP STORM SEWER, CLASS III	LF	221	\$101.00	(\$22,321.00)
3	42" STORM SEWER	LF	305	\$180.00	(\$54,900.00)
4	42" FLARED END SECTION, INCL. TRASH GUARD	EA	1	\$4,800.00	(\$4,800.00)
5	2' X 3' CB	EA	3	\$2,800.00	(\$8,400.00)
6	8' DIAMETER STORM SEWER MH, 8' DEEP, INCL CSTG	EA	1	\$13,000.00	(\$13,000.00)
7	8' DIAMETER STORM STRUCTURE OVERDEPTH	LF	3	\$880.00	(\$2,640.00)
	<b>TOTAL PART 2 DEDUCTIONS</b>				<b>(\$106,061.00)</b>
<b>PART 2 - STORM SEWER MODIFICATIONS (ADDITIONS)</b>					
8	18" RCP STORM SEWER, CLASS III	LF	134	\$58.00	\$7,772.00
9	27" RCP STORM SEWER, CLASS III	LF	67	\$90.00	\$6,030.00
10	36" RCP STORM SEWER, CLASS III	LF	313	\$131.00	\$41,003.00
11	44"x27" RC ARCH PIPE	LF	47	\$190.00	\$8,930.00
12	27" FLARED END SECTION, INCL. TRASH GUARD	EA	1	\$2,600.00	\$2,600.00
13	36" FLARED END SECTION, INCL. TRASH GUARD	EA	1	\$3,800.00	\$3,800.00
14	RANDOM RIP RAP, CLASS III	CY	10	\$81.00	\$810.00
15	4' DIAMETER CBMH	EA	3	\$3,700.00	\$11,100.00
16	5' DIAMETER CBMH	EA	1	\$6,200.00	\$6,200.00
17	6' DIAMETER CBMH	EA	2	\$7,400.00	\$14,800.00
18	6' DIAMETER STORM STRUCTURE OVERDEPTH	LF	3	\$510.00	\$1,530.00
	<b>TOTAL PART 2 ADDITIONS</b>				<b>\$104,575.00</b>
	<b>TOTAL PART 1</b>				<b>\$16,775.00</b>
	<b>TOTAL PART 2 DEDUCTIONS</b>				<b>(\$106,061.00)</b>
	<b>TOTAL PART 2 ADDITIONS</b>				<b>\$104,575.00</b>
	<b>TOTAL CHANGE ORDER NO. 1:</b>				<b>\$15,289.00</b>

Original Contract Amount	\$4,261,887.33
Previous Change Orders	\$0.00
This Change Order	\$15,289.00
Revised Contract Amount (including this change order)	<u>\$4,277,176.33</u>

**CHANGE IN CONTRACT TIMES**

Original Contract Times:  
 Substantial Completion (days or date): August 26, 2022  
 Ready for final Payment (days or date): October 14, 2022

Increase of this Change Order: N/A  
 Substantial Completion (days or date):  
 Ready for final Payment (days or date):

Contract Time with all approved Change Orders: N/A  
 Substantial Completion (days or date):  
 Ready for final Payment (days or date):


Recommended for Approval by:  
**STANTEC**


  
 \_\_\_\_\_

Date: 03/01/2022

Approved by Contractor:  
**KUECHLE UNDERGROUND, INC.**

Approved by Owner:  
**CITY OF MAPLE GROVE**

 Brandon Kuechle  
 \_\_\_\_\_

  
 \_\_\_\_\_

2-11-2022  
 \_\_\_\_\_  
 Date

3/15/22  
 \_\_\_\_\_  
 Date

- cc: Owner
- Contractor
- Bonding Company
- Stantec