



8326 WYOMING TRAIL
CHISAGO CITY, MN 55013
(P) 651.257.6864
(F) 651.257.3393
PETERSONCOMPANIES.NET

March 24, 2022

Maple Grove Middle School
Maple Grove Parks and Recreation Board
Robert Heitke

RE: Softball Netting System

Mr. Robert Heitke,

We have prepared a proposal to furnish and install the Sportsfield Specialties BSS630 StormGuard Netting System at Maple Grove Middle School. Below is a breakdown of the items we have included in our proposal and the exclusions we felt were worth noting.

Base Bid | 30' High StormGuard Netting System

Outfield Southeast Field

- **Netting System**

- Our pricing includes furnishing and installing the Sportsfield Specialties BSS630 StormGuard Netting System. The Southeast Field will have a 30'H x 120'L tension netting system with four (4) 34', 6.625" OD x .280" Powder Coated Steel Poles with a 4' direct embedment. Peterson Companies will be installing the cabling, hardware, and #36 Nylon Netting for complete installation. The bottom of the net will be attached to the top of the 8'H chain link fence. Max pole spacing of 40LF.
- Pricing *INCLUDES* stamped professional engineered foundations.
- Foundation sizes based on manufactures recommended foundation size of 2.5' diameter by 5'-8" deep.
 - This is not the engineered dimension; actual engineering may increase or decrease this size.
- Saw-cut and remove the concrete maintenance strip 5' either side of net pole foundations.
- Remove and dispose of the concrete maintenance strip and related spoils.
- Remove and dispose of fence posts that will not be reinstalled.
- All spoils from our foundations and concrete maintenance strip shall be hauled off-site and disposed of.
- Our pricing includes reinstallation of a 1.5' wide by 10' long concrete maintenance strip to match into remaining strip.
 - Strip will not be doweled into concrete; strip will be free floating.
- All restoration of the outfield grass will be by others.

- **Chain Link Fence**

- Our pricing includes removing and salvaging the chain link fence (rail, fabric, and hardware) as necessary to install the netting system.
- Once the net poles are installed, Peterson Companies will re-install the salvaged chain link fence in-line with the tension netting system poles and existing line posts. The chain link fence will run continuously across the face of the net poles and will not be 'broken up' separately between each net pole. Our pricing includes all necessary hardware, fabric, posts, and rails for complete installation.
 - If School and/or city would be willing to remove all fencing in the area prior to; and after install we would offer a credit of \$4,000.00 for not having to perform this work.

Proposal Total \$51,900.00

Please Note: This is a pole-to-pole tension netting system.

Specific Exclusions: Surveying, field/grass restoration, engineering, and permits.

All proposals exclude subcontractor bonds, bond fees, specialty insurance and workforce or business inclusion goals unless so indicated.

Please feel free to contact me with any questions you may have. We appreciate the opportunity to provide you with this proposal and look forward to working with you on this project.

Sincerely,

Nate Schwaab
Project Manager
651-257-0351